



ASSOCIATED DESIGN GROUP, INC.
A PROFESSIONAL ENGINEERING COMPANY
LAFAYETTE, LOUISIANA

LAFAYETTE OFFICE
114 Toledo Drive
Lafayette, LA 70506
P: 337-234-5710
F: 337-237-1467
www.adginc.org
adginc@adginc.org

ADDENDUM NO. 1

DATE: April 1, 2010

PROJECT: LSUE Hundley Hall
HVAC Cables Replacement Project

PROJECT NO: ADG #09188-2

ENGINEER: Associated Design Group, Inc.
114 Toledo Drive
Lafayette, Louisiana

This addendum to the drawings and specifications for above the referenced project supersedes all contrary and conflicting information contained in said drawings and specifications and are hereby amended in the following particulars and are in full force of this contract:
THIS ADDENDUM CONSISTS OF 1 PAGE(S).

ELECTRICAL ITEMS:

1. Contractor may begin work on Friday May 14, 2010.
2. Contractor shall complete the project by Sunday June 6, 2010.
3. As a point of clarification, the allowable time period for an electrical outage will remain unchanged. The outage may begin at 1:30 pm, Friday May 28, 2010 with power being restored no later than 8:00 pm Sunday May 30, 2010.
4. CLX cable is approved for this project.
5. Wiring may be installed above the existing cable tray. If this method of installation is chosen, the contractor shall extend supports from the existing I-beams leaving a minimum of 12" of clearance above the cable tray. Structural changes shall be sufficient to support the weight of all wiring and accessories. Build new rain shields to cover the existing cable tray and elevated wiring.
6. Contractor shall provide temporary power for the existing Fire Pump and Controls in order to maintain a fully operational system during the utility outage. This work may be performed prior to the utility outage.
7. Contractor is responsible for coordinating the electrical outage and reconnecting with the utility company.
8. Contractor shall store all copper wire in a designated location in Hundley Hall as directed by LSUE personnel. All other construction debris shall be removed from the site by the contractor.
9. Contractor shall verify the size and number of all conduits and conductors to be replaced prior to submitting a bid.

END OF ADDENDUM NO. 1

FOUNDER
Terry Gaudet, PE

K:\PROJECTS\2009\09188-2 Central Plant Raceway Eval Pending Addendum\09188-2 Addendum ELEC 03 04 08 SENT.rpt

CORPORATE OFFICE
114 Toledo Drive
Lafayette, LA 70506
P: 337-234-5710
F: 337-237-1467

MEMBER FIRM OF THE

ACEC
AMERICAN COUNCIL OF ENGINEERING COMPANIES

Website:
adginc.org
Corporate E-Mail:
adginc@adginc.org