TO:	DELIVER TO:	INVOICE TO:
	Bogue Chitto State Park 17409 State Park Blvd Lake Charles, LA 70611	Bogue Chitto State Park 17409 State Park Blvd Franklington
Fax #	Fax # 225 342-9461	

Field Req #	Bid Opening	Delivery Date	F.O.B.	Bid	Manager	Contact #
TVSATINSTAL 1	4/16/10 1:00 PM	20 Days	Park	All	Charlie Gauthier	(225) 342-8111

Description	Line	Qty	Unit	Unit Price	Amount
Installation of a Network High Definition Satellite System in (5) five cabins and (2) two group camps @ Bogue Chitto State Park , also install articulation wall arm and connect to tv in group camps and cabins. Base Bid: Installation will consist of providing each cabin access to Satellite Dish. Installation will include all necessary equipment, tv brackets, power strip, wiring and labor, and shall have a minimum of a 1 year warranty. High Definition signal will be a minimum signal of 50 on transponder 16 of satellite 129 after the software download. Tv's are 32" and 46" Class LCD HDTV, and are furnished by the owner provided to the contractor. To preserve the natural settings of the State Park, furnish as many cabins with the optimum signal required with the fewest number of satellites required.	1	1	job		
Line 2: Contract to show how much per unit, per month for service of these network channels, not to exceed hotel/motel rates: Lodging HD Preferred (Hotel/Motel), Local, ESPN PAK 5 (ESPN HD, ESPN2 HD, ESPNEWS, ESPN CLASSIC, ESPNU), Add-on #11(Comedy Central, MTV, MTV2, Nickelodeon, TV LAND, VH1, VH1 Classic, MHD), and Action Pkg (DIY, Military Channel, Outdoor Channel, The Golf Channel, Speed, Tennis Channel HD, Versus, Golf/Versus HD). Local Network: Nearest to closet city in Louisiana.	2	1	month		
** See Attached Specs ** This is an all or nothing bid. Please contact Charlie Gauthier (225) 342-8111 with any questions. *** MANDATORY PREBID: April 13, 2010 @ 10:00 AM AT Bogue Chitto State Park Insurance Requirements Vendor must supply certificate of liability insurance to enter park gates.					

SUB-TOTAL						

Initial Here:

Fax bid to (225) 342-9461 before 4/16/2010 2:00 PM						
TOTAL						

Conditions

1) Read the entire bid, including all terms, conditions and specifications. Note any attachments referenced in description.
2) All bid prices must be typed or written in ink. Any corrections, erasure or other forms of alteration to unit prices should be initialed by bidder.
3) This bid is to be manually signed in ink by a person authorized to bind the vendor and faxed back to the agency.

4) Bid opening is the date and time by which all bids shall be received in order to be considered.

5) "Bid" is the type of Bid - "All" means the bid will be considered on the vendors ability to supply **all** lines listed. "Line" means the bid will be considered on the ability to supply

6) Bid prices shall include delivery of all items F.O.B. destination or as otherwise provided.

7) Bids must be received at the "Deliver To Fax #" specified in the solicitation by the bid opening date in order to be considered. Retain you fax bid confirmation sheet in order

8) Unless otherwise specified by the State of Louisiana in the solicitation, bid prices must be complete, including transportation prepaid by the bidder to the destination and firm

9) Vendor is responsible for including all applicable taxes in the bid price. State agencies are exempt from all state and local sales and use taxes.

10) All bids, unless otherwise provided for, must be signed, submitted and in accordance with these forms provided in the same manner they were received. Failure to do so will

11) Bidders proposing an equilavent brand or model should submit illustrations, descriptive literature, technical data with the bid forms sufficient for the State of Louisiana to

Company Name: _____

Delivery Date: _____

Contact & Phone: _____

Signature: _____

By signing above I understand and agree to all terms and conditions set forth above.

Scope of Work:

Installation of a Network High Definition Satellite System in (5) cabins and (2) group camps @ Bogue Chitto State Park, also install articulation Wall Arm and connect to TV

1. Base Bid: Installation will consist of providing each cabin access to Satellite Dish. Installation will include all necessary equipment, wiring and labor, and shall have a minimum of a 1 year warranty.

   High Definition signal will be a minimum signal of 50 on transponder 16 of satellite 129 after the software download.

   TV's are 32" and 46" Class LCD HDTV, and are furnished by the owner provided to the contractor.

   To preserve the natural settings of the State Park, furnish as many cabins with the optimum signal required with the fewest number of satellites required.

2. Line 2: Contract to show how much per unit, per month for services of these network channels, not to exceed hotel/motel rates: Lodging HD Preferred (Hotel/Motel), Local, ESPN Pak 5 (Espn HD, ESPN2 HD, ESPNEWS, ESPN CLASSIC, ESPNU), Add-on #11 (Comedy Central, MTV, MTV2, Nickelodeon, TV Land, VH1, VH1 Classic, MHD), and Action Pkg (DIY, Military Channel, Outdoor Channel, The Golf Channel, Speed, Tennis Channel HD, Versus, Golf/Versus HD). Local Network: Nearest to closest city in LA.

02802 Poles

The contractor shall supply, if necessary for the use of remote satellite mounting, 2-3/8 inch round or 3 inch square by 16 feet metal post. Post shall be colored by powder coating to match surroundings and straight for the entire length. Poles shall be placed four (4) feet into the ground with a minimum of six (6) inches of space in all directions between the pole and the surrounding ground.
Concrete shall be used to backfill the holes to within eight to twelve (8-12) inches from the ground surface. Remaining backfill shall be soil material matching as closely as possible the surrounding soil type. Placement of the poles will be determined at the pre bid.

02810 Electrical Power

Contractor shall run #12 Romex from existing panel in a manner as to conceal, (i.e. in attic, in existing wall), win which the outlet box is hidden behind the TV. NO WIRES EXPOSED (location of installation will be discussed with awarded vendor)
Provide an inline Cable/Sat Protection, Which will protect equipment from electrical surges that travel over cable, satellite, and antenna lines.

02803 Underground Conduits

If necessary to remote locate the satellite, use underground conduit to run the RG6 Cable to structure. Replace any sod or tree in like kind. Provide the necessary trenching equipment and back bury the trenched cable. Trenched will be approximately 8" to 12" and all cable to be set in conduit.

106071 Metal Brackets

Use Promounts or equal to mount TV and TV cable box (mount boxes underneath in articulating wall arm connector.