



Purchasing Department

Purchasing Department
P.O. Box 9534
Baton Rouge, LA 70813
Phone: (225) 771-4580
Fax: (225) 771-2026

Addendum Number # 2

April 3, 2024

DEMONSTRATION FARM

SU Ag Center

Southern University and A&M College
Baton Rouge, Louisiana 70813

Bid # 10317

10:30 A.M.

April 25, 2024

The following modifications to the referenced project shall be incorporated into the original specifications and/or plans. Unless a change is specifically made by addendum, the specifications and/or plans as issued shall govern.

Bids shall be accepted in the Purchasing Department by above date and time

Note: Vendors are required to acknowledge receipt of this addendum on the Louisiana Uniform Public Work Bid Form

Attachments:

- Clarifications
- Information for Base Bid and Alternate # 1

A handwritten signature in blue ink that reads 'Linda Antoine'.

Linda Antoine, Director of Purchasing

Date

4/3/2024

Thompson Luke & Associates, L.L.C.

10705 Rieger Road, Suite 101
Baton Rouge, LA 70809
225.293.9474



Southern University Demonstration Farm
9202 B.A. Little Drive, Baton Rouge, LA 70813
Engineer Proj. Number: 22-242

ADDENDUM #2

The following items shall be considered part of the Contract Documents for the above referenced project and shall take precedence over any conflicting statements contained therein. Revise all other notes, schedules, details, elevations, and sections as required.

General Clarifications:

1. Contractor shall provide a base bid price and a separate alternate #1 price. Base bid shall include the entire project including architectural, civil, mechanical, and electrical items. This base bid price includes the mulch around the raised planter beds. The alternate price shall be a separate price that replaces the mulch with 8" WoodCarpet Engineered Wood Fiber System 1 or equal over manufacturer-recommended geotextile fabric over 4" manufacturer-recommended gravel.
2. Areas indicated as "New Planting Bed" shall be cleared of grass & 6" of top soil. New planting beds shall be surrounded by 6" heavy steel edging. Refer to addendum 1, clarification #17 for more information. Contractor shall provide 6 oz super geotextile non-woven fabric to be used in the planting beds. The planting beds will be left open to be filled by owner with mulch and desired plants. The large planting bed on the west side of the pavilion shall only be removed of grass and 6" of top soil. No geo fabric is necessary for the large planting bed only. The steel edging will only be necessary in between the large planting bed and the limestone path. Refer to the architectural sheet A1.3 for details of metal edging.
3. The existing site soil can be re-used to backfill over new drainage pipe.

If you have any questions, please contact our office.

Thompson Luke & Associates, L.L.C.
A Professional Engineering Company

Thompson Luke & Associates, L.L.C

10705 Rieger Road, Suite 101 | Baton Rouge, LA 70809 | P: 225.293.9474